


Technical drawing of a garden bed plan. The drawing shows a rectangular garden bed with a width of 3.50m to 4.00m and a length of 1.50m. The bed is filled with a green pattern representing grass. The bed is bordered by a concrete support (opornik bet. 12x25 cm) and a curb (krawężnik 15x30 cm). The drawing includes elevation levels: +0.06, +0.02, and 0.00. A section line A-A is indicated. The drawing also shows the location of existing gates (2* istniejąca rzędna bramy) and the low green lawn (zielen niska - trawnik).

skala 1:10



1. KRAWĘŻNIK BETONOWY 15*30
2. PODSYPKA CEM-PIASKOWA 1:4 GR. 3-5 cm
3. ŁAWA BETONOWA Z OPOREM C12/15
4. KOSTKA BRUKOWA BETONOWA KOLOROWA GR. 8 CM
5. PODBUDOWA Z KRUSZYWA ŁAM. STAB. MECH. GR. 15 CM
6. GRUNT STAB. CEM., $R_m=2,5N/mm^2$, GR. W-WY 15 CM

INWESTOR	MIASTO MAKÓW MAZOWIECKI 06-200 Maków Mazowiecki, ul. Stanisława Moniuszki 6			
JEDNOSTKA PROJEKTOWA	"USŁUGI PROJEKTOWE WIKTOR ŁYSKO" ul. B. Prusa 10, 06-200 Maków Mazowiecki			
ZAMIERZENIE BUDOWLANE	MODERNIZACJA ULICY SPORTOWEJ			
TYTUŁ RYSUNKU	ZJAZD INDYWIDUALNY BRAMOWY			
STADIUM	PROJEKT WYKONAWCZY			
Nr rys. 3	skala: schemat	data: listopad 2022		
	Imię i nazwisko	Uprawnienia	Podpis	
PROJEKTOWAŁ	Wiktor Łysko	w spec.konst.-inż. w zakr. drog 153/93 /0s		

Niweletę krawędzi zjazdu B-B należy dostosować do istniejących rzędnych nawierzchni na posesji.